



LOCATION MAP

LATITUDE: 41° 04' 56" N, LONGITUDE: 81° 38' 37" W

SCALE IN FEET



COUNTY OF SUMMIT CLEVELAND MASSILLON ROAD COUNTY HIGHWAY 17 P.I.D. # 108468 F.A.N. # E191200 COPLEY TOWNSHIP

STAGE 3 SUBMITTAL 01-22-2021

PROJECT DESCRIPTION

ROADWAY MINOR REHAB - EXISTING ROADWAY TO BE MILLED AND OVERLAID FROM APPROXIMATELY 400 FEET NORTH OF MINOR ROAD TO EAST LEG OF RIDGEWOOD ROAD, OMITTING THE 640-FOOT PORTION PREVIOUSLY IMPROVED AT COPLEY CIRCLE AND AT RAILROAD CROSSING. SUBSTANDARD SHOULDERS WILL BE WIDENED AND IMPROVED WHERE POSSIBLE. PROJECT LENGTH IS 1.81 MILES.

EARTH DISTURBED AREA

PROJECT EARTH DISTURBED AREA: 1.14 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 1.00 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA: 2.14 ACRES

2019 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

INDEX OF SHEETS:

GENERAL NOTES	2-5
SCHEMATIC PLAN	6
TYPICAL SECTIONS	7-8
RESURFACING PLAN	9-28
PROJECT SITE PLAN	29-30
GENERAL SUMMARY	31-33
INTERSECTION DETAIL & GUARDRAIL DETAIL	33
PAVEMENT MARKING	34-39
DRIVEWAY PLAN AND SUBSUMMARY	40-41

DESIGN DESIGNATION

NHS PROJECT	N/A
FUNCTIONAL CLASSIFICATION	MINOR ARTERIAL ROADWAY
CURRENT ADT - SOUTH/NORTH PROJ. LIMITS	8423/12435
DESIGN/LEGAL SPEED - FROM BEG. PROJECT TO 0.6 MILES S. OF SR 162	45/45 MPH
DESIGN/LEGAL SPEED - FROM 0.6 MILES S. OF SR 162 TO END PROJECT	35/35 MPH
DESIGN EXCEPTIONS	NONE

UNDERGROUND UTILITIES

CONTACT BOTH SERVICES
CALL TWO WORKING DAY
BEFORE YOU DIG



Know what's below.
Call before you dig.

OIL & GAS PRODUCERS PROTECTIVE
SERVICE CALL: 1-800-925-0988

PLANS PREPARED BY:

Environmental Design Group
AKRON / CLEVELAND / COLUMBUS
HQ 450 GRANT ST., AKRON, OH 44311
P 330.375.1390 / TF 800.935.1390
W ENVDESIGNGROUP.COM

ENGINEERS SEAL

SIGNED: _____
DATE: _____

STANDARD CONSTRUCTION DRAWINGS				SUPPLEMENTAL SPECIFICATIONS			
BP-3.1	01/17/2020	MGS-1.1	01/19/2018	TC-41.20	10/18/2013	800	01/15/2021
BP-5.1	01/18/2019	MGS-2.1	01/19/2018	TC-42.20	10/18/2013	832	10/19/2018
BP-7.1	01/17/2020	MGS-4.2	07/19/2013			875	01/18/2019
CB-1.1	07/19/2018	MGS-5.3	07/15/2016	TC-71.10	01/19/2018		
				TC-82.10	07/19/2019		
DM-4.4	01/15/2016	MT-97.10	04/19/2019				
		MT-97.11	01/20/2017				
		MT-99.20	04/18/2019				
		MT-101.90	07/17/2020				
		MT-105.10	01/17/2020				

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING OF TRAFFIC OF THE HIGHWAY AND THAT THE PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____

DATE _____ SUMMIT COUNTY ENGINEER

APPROVED _____

DATE _____ SUMMIT COUNTY ENGINEERING DEPT.

FEDERAL PROJECT NO.	E191200
CONSTRUCTION PROJECT NO.	NONE
RAILROAD INVOLVEMENT	NONE
PID NO.	108468
CLEVELAND MASSILLON ROAD RESURFACING	